BRUHATH BANGALORE MAHANAGARA PALIKE, DASARAHALLI ZONE

Office of the Executive Engineer Dasarahalli Division,

No.BBMP/EE/DD/Ten/06/2013-14, Date:05.11.2013 **ITEM NO: 05**

SCHEDULE-B

NAME OF WORK: Pot Holes Filling in ward No.12, in Shettyhalli Sub Division.

Sl. No	Description of work	Unit	Qty	Rates Quoted by Contractor **LAKSHMINARAYANA K L**		
				In Figures (Rs.)	In Words (Rs.)	AMOUNT
1	2	3	4	5	6	9
1	Earthwork excavation by manual means in ordinary soil involving an average horizontal throw upto 2 meters and an average lift upto 0.5 m, excavated surface leveled and sides neatly dressed the disposed earth to be leveled neatly after breaking of clods complete as per specifications.	Cum	295.74	66.0	Rupees Sixty Six Only	19518.84
2	Providing, laying, spreading and compacting graded stone aggregate to wet mix macadam Specifications including premixing the material with water at OMC in mechanical mix plant carriage of mixed method of tipper to site, laying in uniform layers with paver in sub-base/base course on well prepared surface and compacting with vibratory roller to achieve the desired density complete as per Specifications.	Cum	295.74	1057.0	Rupees One Thousand Fifty Seven Only	312597.18
3	Tack coat:- Providing and laying tack coat with bitumen emulsion using emulsion pressure distributor at the rate of 0.20 kg per sqm on the prepared bituminous/Granular surface cleaned with mechanical broom. Complete as per specifications.	Sqm	1478.7	14.0	Rupees Fourteen Only	20701.80
4	Filling Pot-Holes and patch repairs with Bituminous Concrete, 40mm., KSRRB M3000-5. Removal of all failed material, trimming of completed excavation to provide firm vertical faces, cleaning of surface, painting of tack coat on the sides and base of excavation as per clause 500.3, back filling the pot holes with hot bituminous material as per clause 500.4, compacting, trimming and finishing the surface to form a smooth continuous surface, all as per clause 3004.2 complete as per Specifications.	Sqm	1478.7	410.5	Rupees Four Hundred Ten and Fifty Paise Only	607006.35

For Vinyas Builders

Partners

Signature of the Contractor

Executive Engineer

ಕಾರ್ಯನಿರ್ವಾಹಕ ಅಭಿಯಂತರರ
ಬೃಹತ್ ಬೆಂಗಳೂರು ಮಹಾನಗರ
ದಾಸರಹಳ್ಳಿ ವಲಯ, ಬೆಂಗಳೂರು

5	Disposal of debris to the final place of disposal with all lead and lift and as direction by the engineer in charge of the work, lead 10 Km a)Basic rate for haulage of materials as per item No. 17.4/KSRRB : M100-4.1 ..... Rs. 2.00 Tonne/Km b)Average earth of work 1.28 Tonne/Km for Rs. 2.00/Km c)Add loading and unloading complete as per specifications.	Cum	293	69.0	Rupees Sixty Nine Only	20217.00
					Total	980041.17
					Percentage	-1.99%

For Vinyas Builders

Partners

Signature of the Contractor

Executive Engineer,
Dasarahalli Division,